CAIRNGORM FUNICULAR RAILWAY VIADUCT STRENGTHENING REPORT






ADDRESS COWI UK Limited Bevis Marks House 24 Bevis Marks London EC3A 7JB TEL +44 207 9407 600 WWW cowi.com

JUNE 2019 HIGHLANDS AND ISLANDS ENTERPRISE

CAIRNGORM FUNICULAR RAILWAY VIADUCT STRENGTHENING REPORT



CONTENTS

1	Executive Summary	5
2	Introduction	6
2.1	Scope of study	6
2.2	Summary of appraisal	6
3	Alternatives to strengthening	7
3.1	Reduced loading	7
3.2	Load testing	7
3.3	Whole or partial replacement	7
4	Basis of strengthening	9
4.1	Design criteria	9
4.2	Design life	10
4.3	Extent of strengthening	10
5	Proposed strengthening details	12
5.1	General	12
5.2	Piers	12
5.3	Anchor blocks	12
5.4	Bearings	13
5.5	Beam shear strengthening	14
5.6	Continuity strengthening	15
6	Budget estimates	16
6.1	Estimating method	16
6.2	Construction cost	16
6.3	Commentary	17
6.4	Further development	17

7	Safety and environment	19
7.1	Health and Safety	19
7.2	Sustainability and Environment	19
8	Conclusions	20
8.1	Summary	20
8.2	Further work	21

APPENDICES

Appendix A	Testing details
Appendix B	Technical notes
Appendix C	Strengthening scheme details
Appendix D	Strengthening scheme extents
Appendix E	Health, Safety and Environment
Appendix F	Cost estimate and programme for construction

1 Executive Summary

An appraisal report A116993-RP01 v2 and addendum to this report A116993-RP02 Addendum A1 concluded the viaduct supporting the Cairngorm Funicular Railway to be unable to support its original design loadings in its current condition. Key deficiencies are main beams which are overloaded in shear, bearings which are overloaded and misaligned, and piers which are overloaded in bending.

A concept strengthening scheme has now been developed. This comprises the following:

- > installation of permanent props to approximately 50% of the piers,
- replacement of all bearings,
- installation of extra bearings at most anchor blocks,
- strengthening the existing concrete beams with external bars bars are to be installed at all scarf joints, further into the span on approximately 40% of beams and over almost the full span length on 5% of beams.
- > reinforcing some beam to beam connections to improve durability.

In addition to the strengthening, changes to emergency procedures are recommended to address the risk of bearing uplift.

The estimated construction cost of the strengthening is \pounds 5.85 million +/-20%. Two options for strengthening are considered - an option in which construction would be expected to take place over two summer seasons with completion in October 2021, and an option in which construction takes place in one season with completion in November 2020.

Alternatives to strengthening exist. Options include operating under reduced loading after partial strengthening, load testing to reduce the extent of strengthening, and whole or partial replacement of the viaduct.

2 Introduction

2.1 Scope of study

An appraisal of the viaduct supporting the Cairngorm Funicular Railway has found that in its current condition the structure is unable to support its original design loadings. Operations are currently suspended.

The objective of this study is to develop outline proposals for strengthening in order to determine a budget price and programme for remedial works which would allow the funicular to resume operation. This report describes the proposed strengthening and the budget price. Producing a detailed strengthening scheme for check and procurement or discussing the proposals with the regulatory authorities is not part of COWI's current scope.

2.2 Summary of appraisal

COWI UK Limited undertook an appraisal of Cairngorm Funicular Railway. A description of the facility and the appraisal is contained in the appraisal report A116993-RP01 v2 and addendum to this report A116993-RP02 Addendum A1.

Element	Deficiency
Main beams	Many spans are overloaded in shear
	Risk that all scarf joint have deficient shear strength
	5 spans are overloaded in hog bending where cast into anchor blocks
	Cracking especially at piers which could lead to reinforcement corrosion and hence a further loss of strength in future
Bearings	At low temperatures some bearings will travel beyond extent of sliding surface due to misalignment
	On all spans vertical and lateral load capacity is exceeded
	Bearings are unable to resist uplift
Piers	Crossheads are overloaded in the steepest part of viaduct
	Columns overloaded in bending and shear on the taller piers
	Piers have low resistance to collision load and could fail if impacted
Pier foundations	Many piers are thought to have rotated due to the inclined bearing loads. Rotation will have occurred over operational lifetime to date and is treated as irreversible.

The appraisal identified the following deficiencies:

Table 1

Summary of deficiencies identified in the appraisal

3 Alternatives to strengthening

3.1 Reduced loading

Some elements of the strengthening could be avoided if reduced loading was adopted. This could include a limit on passenger numbers in the carriage. However, not all strengthening could be avoided, and robust operating procedures would be needed to ensure these limits are enforced. This approach does not eliminate any risk of damage to the structure in either of the storm condition load cases.

3.2 Load testing

The scarf joints in the main beams contain unusual details for which strength cannot easily be determined. Therefore, the strength of these joints is uncertain. These joints have been identified as at risk of failure rather than being substandard.

As an alternative to strengthening, the joints could be load tested to determine the existing strength of the detail. If a representative sample of joints pass the load test, this would provide good evidence that the joints are not substandard. With agreement of the regulatory bodies, strengthening could be avoided using this approach. However, there is a risk joints could be damaged by the load test, and consequently extra remedial work needed in addition to strengthening.

A possible testing scheme is shown in Appendix A. The likely number of load tests to achieve a representative sample across the viaduct would be in the order of 10-15 joints. Note that not all joints would be tested and thus residual risk would be mitigated by an appropriate selection of testing areas and testing rig set-up.

3.3 Whole or partial replacement

It is understood that the mechanical and electrical elements of the facility are nearing the end of their design life and hence need to be replaced in the near future.

As an alternative to strengthening, the whole structure could be replaced.

To reduce the scope of strengthening the deck (i.e. everything above the bearings) could be replaced, keeping the existing piers, anchor blocks and foundations. The new deck could be lightweight, reducing loads on the substructures, but if new bearings are used with the same arrangement as the existing bearings then it is likely that much of the pier strengthening will still be required.

If a new deck were to be built with a different bearing arrangement as described in Appendix B then strengthening of the substructure could be avoided. It is not

thought to be practical to in install the different bearing arrangement without replacing the deck.

Although this remains an option, the extent and thus cost of this scheme would be expected to be substantially more than strengthening the existing structure. At this stage examining the feasibility of whole or partial replacement is not part of COWI's scope.

4 Basis of strengthening

4.1 Design criteria

Only those parts of the structure that have failed the appraisal to assessment standards are to be strengthened. Parts to be strengthened will be designed to comply with modern design standards, i.e. Eurocodes.

The strengthening is designed to accommodate the design loads, limiting temperatures and wind speeds used in the original design and the appraisal. Hence the strengthened structure should satisfy the following criteria:

Carriage weights:

>	Empty carriage:	14,900 kg	
>	Maximum payload:	9,600 kg	(120 persons at 80 kg per person)
>	Hence total:	24.500 kg	

Shade air temperature limits in operation or out of operation:

>	Minimum:	-29 °C

Maximum: +27 °C

Maximum wind gust speeds:

- In operation: 35 m/s
- > Out of operation: 75 m/s at top station, 56 m/s at bottom station

Design situations considered in the design:

- > In operation: Fully laden moving carriage + wind at 35 m/s.
- Evacuation: Empty static carriage + 5000 kg kentledge + wind at 50 m/s.
- Storm: No carriage + maximum out of operation winds.
- Accidental: Empty static carriage clamped to rails + 5000 kg kentledge + maximum out of operation winds.

In accordance with Eurocodes, loads in the accidental design situation are unfactored. This differs from the approach taken in the original appraisal. Justification for this is given in the addendum to the original appraisal. These design criteria for concept design would need to be developed into a full basis for design (in the form of an Approval in Principle or similar document) if the design is to progress to detailed design.

4.2 Design life

The original design life is not known. A draft version of EN 13107 is referenced on the original design certificate but that version of the standard is no longer available.

The current version of BS EN 13107 recommends the following design lives for civil engineering elements of funicular railways:

- 20 years for bearings,
- > 50 years for the remainder of the supporting structure.

Strengthening proposals are intended as a "long term" solution to the structural deficiencies identified, and therefore there is an intent to achieve the design lives given above in all areas of intervention. However, this cannot be guaranteed for the whole structure as the design is constrained by the existing structure and there is the possibility that new defects in the existing structure may manifest themselves in the future. The risk of further defects has been minimised by non-destructive testing and detailed structural appraisal but cannot be eliminated completely.

Existing undesirable design details and areas of construction which do not comply with the apparent design intent are present in the as-built structure. These undesirable details have led to faster than expected deterioration in the life of the structure to date and will compromise the future design life and durability. The strengthening scheme seeks to address the most significant of these details but enhanced inspection and maintenance procedures are likely to be required to ensure that the design life is maximised.

4.3 Extent of strengthening

Based on the appraisal result the extent of the strengthening scheme is as shown in Appendix D and summarised as follows:

- > A total of 43 out of 88 piers are to be strengthened,
- 5 of the 6 anchor blocks are to be strengthened,
- All 196 bearings are to be replaced, (2x93 at piers/anchor blocks 1 to 93, +8 extra at passing loop, +2 at tunnel portal),
- A total of 97 new lateral guide bearings to be added to all piers, (1x93 piers/anchor blocks +3 extra at passing loop, +1 at tunnel portal),

- All beams are to be strengthened at all 360 scarf joints (4x87 piers, +12 extra at passing loop),
- A total of 166 beam ends are to be strengthened at the 1st crossbeam position (2x77 span ends, +12 extra at passing loop)
- A total of 20 beam ends are to be strengthened from the 1st crossbeam up to the 2nd crossbeam positions (2x2+2x3=10 each end of passing loop)
- 13 type 3 to type 3 beam hog connections are to be strengthened (4x2 at piers 46 to 50, +5 more in passing loop).

The above extents need to be confirmed as part of the detailed design and check process, and hence while the above quantities are appropriate for concept design and pricing of the strengthening scheme, quantities may be adjusted up or down as the design progresses.

5 Proposed strengthening details

5.1 General

The following sections describe the proposed details for the concept design. At this stage detailed design and check have not been undertaken. All details and extents need to be confirmed as part of the detailed design and check process, and hence while these details are considered appropriate, there is a risk that details will change.

5.2 Piers

The proposal is to strengthen the piers with inclined props as shown in sketch SK01 rev A in Appendix C. A total of 43 of the 88 piers are to be strengthened as shown within the scheme extents in Appendix D. The piers to be strengthened are generally the taller piers.

It is proposed to use the PERI HD-200 lightweight aluminium or steel system as the main prop elements. The props would be installed tight, but without any significant preload. Hence there is no expectation that the props push any piers back to the vertical position.

The propping is beneficial for the following reasons:

- the existing pier foundations are prevented from further rotation, which is thought to be the cause of the current bearing misalignments,
- the bending moments and shear forces in existing pier columns under imposed loads will be considerably reduced,
- > shear in the crosshead outstands will be considerably reduced,
- propped piers will have much greater resistance to impact loads, especially from below, though the props themselves will be vulnerable.

One alternative option was considered but discounted. This was to surround the column pier with an offset concrete jacket which would strengthen the column and restore its stability. While this could achieve all the above aims, the prop proposal is thought to be more effective at preventing further rotation of the foundations, modular in nature and thus more buildable and cheaper to construct.

5.3 Anchor blocks

The proposal is to install additional bearings under the beams just above the anchor blocks as shown in sketches SK12 and SK13 in Appendix C. Five of the six anchor blocks require these additional bearings as shown within the scheme extents in Appendix D.

Laminated elastomeric bearings are proposed. In three of the five locations the new bearings can be supported on the anchor block as shown in SK12. In the remaining two cases the new bearings would be beyond the edge of the anchor block, so a new steel frame is proposed as shown in SK13. Steel frames have been chosen for ease of installation.

The additional bearings work by reducing bending moments in the beam ends that are cast into the anchor blocks. The elastomeric bearings are soft enough to provide sufficient support to live loads without causing the beam ends to rip out of the anchor blocks.

One alternative option was considered but discounted. This was to expose the end of the beam reinforcement extending into the anchor block and connect an extension bar anchored into the main body of the anchor block. While this would achieve the objective, access to the area is blocked by the rail expansion joints, and major works to remove and replace rails would be necessary to enable this option. There is also a significant risk associated with unknown construction details within the existing structure being exposed during any intrusive works. It was deemed more appropriate to mitigate this risk by adding to the existing structure and minimising any intrusive interventions.

5.4 Bearings

The proposal is to replace the existing two bearings at each pier and anchor block with three new bearings as shown in sketch SK05 rev A in Appendix C. All bearings are to be replaced.

An additional new third central bearing is to carry the lateral load only while outer bearings carry vertical load only.

The new bearings are needed for the following reasons.

- > the existing bearings are thought to be significantly overloaded,
- > many of the bearings are now misaligned, and replacement is the only realistic option to prevent them sliding beyond the extent of their sliding surfaces.

No valid alternative options to the three-bearing arrangement have yet been identified. Despite extensive efforts involving bearing suppliers a solution for replacement with just two new bearings at every pier has not been found (refer to Appendix B for more detailed technical information). The difficulty is designing a bearing to carry the required combination of high lateral and low vertical loads, while fitting within the space available using the existing bearing fixing centres. Further design development may show that it is possible to replace with two bearings for areas below the passing loop where wind loads are less severe, but this has not yet been proven. The remaining problem identified in the appraisal is that the bearings have no resistance to uplift. The proposal is not to design new bearings for uplift but instead to revise emergency procedures.

Uplift only occurs under the accidental design situation for the areas in and above the passing loop. Currently, in the event of a breakdown and an approaching storm, the emergency procedure is to clamp the carriage to the tracks and install a 5 tonne kentledge in the carriage. This prevents the carriage wheels lifting off the track but in areas above the passing loop does not prevent the bearings uplifting off the piers. A revised emergency procedure might include either some sort of tie-down between deck and pier, or to install a greater weight of kentledge.

Alternative solutions to the uplift problem have been considered. Uplift bearings are available, but as the fixings to the beam and to the pier crossheads do not have any capacity for uplift, no benefit would be achieved. Other options are to accept uplift providing this does not lead to instability or damage, or to accept the risk of damage on the basis that no-one's safety is at risk during such an extreme event.

The implications of any of the approaches noted above needs further consideration between operator, designer and regulatory bodies. Management of residual risk may prove an appropriate mitigating method to reduce whole life costs for the funicular in managing an extreme, rare event.

5.5 Beam shear strengthening

The proposal is to strengthen the main deck beams with external bars as shown in sketches SK14 and SK15 in Appendix C. Beams at all 88 piers have scarf joints and all are to be strengthened as shown in SK14 - a total of 360 joints. Many beams are also to be strengthened at the first crossbeam as shown in SK15, and some beams are to be strengthened up to the second crossbeam. Strengthening locations and scheme extents are given in Appendix D.

The strengthening comprises a series of galvanised yokes and stainless steel preloaded bars installed perpendicular to the rails at around 450mm spacing, fitted between the track supports which are at nominal 900mm spacing.

The strengthening works as follows. According to the "truss analogy" used in reinforced concrete design, concrete webs develop tension when subject to shear. In this structure the shortfall in shear strength along the length of a precast beam is due to a lack of reinforcement in the beams. This reinforcement is intended to resist tension within the section. By pre-compressing the concrete, the concrete can carry much more shear before the web develops net tension.

Several alternative options were identified but discounted as follows:

Extended bearing plates could have been used at scarf joints to reduce the quantity of strengthening, but these would not have been simple to install and would occupy space needed for new bearings. This would not address strengthening the scarf joints but may have prevented disproportionate collapse in the event of a failure of the scarf joint.

- Longitudinal prestress bars could have been used to relieve shear near the ends of beams, but there were difficulties finding practical ways to connect the prestressed bars to the concrete beams.
- Internal reinforcement could be added to be beams, but this requires very extensive site work including hydro demolition and insitu concreting. The extent of site work coupled with the significant risks of intrusive interventions to a structure with unknown as-built construction details, led to this option being discounted.
- Fibre reinforced plastic (FRP) wraps could be added to the beams, but this also requires extensive site work including insitu concreting. Wrapping FRP would prove difficult given the constraints of the rail on the top flange.

5.6 Continuity strengthening

The proposal is to install new reinforcement where type 3 beams are connected at piers. The new bars will be within the insitu concrete at the piers but connected to existing reinforcement in the beams. A total of 10 of the 88 piers are to be strengthened in this way as shown in sketch SK11 in Appendix C. These are locations where the track is tightly curved in plan and concentrated at and below the passing loop.

The benefit of the new bars is greater control of cracking at these piers and hence an improvement in future durability. Currently there is a lack of reinforcement continuity and large cracks have been observed. The new bars cannot prevent cracking but will control crack widths to a width that reduces future corrosion.

An alternative option is simply to omit this element of the strengthening, and accept the risk of future deterioration. These bars are not needed for strength.

6 Budget estimates

6.1 Estimating method

The strengthening cost estimate is based on the extents described in section 4.3 above and the details described in section 5 above.

The cost estimate for the strengthening has been determined with the assistance of BAM construction. Two versions have been considered, one with construction spread across two summer seasons and one with construction in a single summer season only. The full report including all assumptions and outline programmes are given in Appendix F.

The following key assumptions were made:

- In the two season option the strengthening is constructed over 2 summers: 2020 and 2021, the summer season extending from late May to late October. This includes approximately 5 weeks terminal float.
- In the single season option the strengthening is constructed in the summer of 2020, from early April until late November. This also includes 5 weeks float.
- A review of using a temporary cableway similar to that used in construction proved prohibitively expensive. Helicopters are used to transport materials from a base at the bottom car park to the work sites. In the version with construction in one season, two helicopters would be required at peak periods. The funicular is not available to assist with construction, and no temporary cableway is installed. The single season option relies on the use of purpose built rail mounted lifting trolleys.
- Excavations for foundations are generally carried out by low ground pressure excavators below the passing loop and spider type excavators above the passing loop. All excavations are made good after completion of the works to restore the existing surface material.
- > Surplus excavated material is not disposed off-site.

6.2 Construction cost

For either the two season or one season versions, the estimated cost is £5.6 million with a +/-20% margin of error excluding the material cost of the vertical load bearings. This is estimated to add £0.25 million giving a total of £5.85 million +/-20%. The estimate includes 5% for risk and is based on 3.7% Retail Price Index.

6.3 Commentary

The cost estimating exercise is derived using assumptions on productivity, material availability and construction sequencing and methods. Commentary on BAM's report and programmes are included in Appendix F.

Clearly construction over single season requires simultaneous working at more work fronts than the two season option. The two options are the same cost, but the sensitivity to cost increases for weather downtime will be higher for the single season option due to the higher resource levels that are needed on site in order to achieve the accelerated programme.

The single season option is based on an earlier start and later finish than the two season option. Therefore the single season option carries significantly greater weather risk than the two season option, and there is potential overlap with the ski season.

As discussed in section 4.2, enhanced inspection and maintenance will be required to mitigate any accelerated deterioration of the structure but this comes at a cost. No whole life costing has been included in this study for any operator in the future. These long terms costs need consideration when strengthening an existing structure. Assets of the nature of the funicular railway benefit from pro-active management.

The estimate provided is for construction costs only. Additional costs which are not accounted for in this estimate include:

- Project management
- > Detailed design and independent check
- > Tender document drafting to enable procurement.
- Costs of approvals and liaison with regulators and stakeholders
- Site supervision and designer liaison to address queries or unexpected conditions during construction.

6.4 Further development

To refine the budget estimate the following items could be developed further:

- In view of the considerable cost of helicopter deliveries, reconsider the possibility of using the funicular to aid construction.
- Considerable cost reductions would be achieved by minimising the volume and depth of concrete foundations. This would be a priority for design development of this element of the works.

Develop bearing designs further to try to eliminate the need for the central bearing in some areas of the viaduct.

COWI recognise that the impact on the local area of the closure of the funicular is significant and the prospect of the closure extending until the end of 2021 is likely to be of great concern. Full unrestricted re-opening of the funicular before the end of 2020 at the earliest carries considerable risks due to the assumed construction period and associated weather risk. These need consideration whilst managing the expectations of the community and public. Even with adequate risk management and contingencies in place during the single season construction programme, there remains a significant risk that environmental conditions experienced on site would prevent achieving this programme.

7 Safety and environment

7.1 Health and Safety

As a designer under the Construction (Design and Management) Regulations 2015, commonly referred to as the CDM Regulations, COWI UK has the following duties at this stage:

- a duty to consider how health and safety risks encountered during construction, maintenance and eventual demolition can be reduced or eliminated;
- a duty to provide information about health and safety risks which cannot be eliminated.

To discharge these duties, COWI UK has assessed health and safety risks and compiled a designer's risk register for the concept design, together with a design decisions log. These are included in Appendix E.

As a designer, COWI must also make the client aware of their obligations under the regulations. COWI have contacted HIE separately regarding their obligations. We further note that a Principal Designer must be appointed before design proceeds to the next stage.

7.2 Sustainability and Environment

The Cairngorm Funicular Railway is situated in a Site of Special Scientific Interest (SSSI) and hence any ground works is highly undesirable.

The most environmentally sustainable strengthening solutions are generally those that preserve existing assets as far as possible. The proposed strengthening to piers and anchor blocks is necessary to achieve this, and hence some ground works are inevitable.

On this project access to work sites is difficult owing to the sloping ground. Some temporary access roads may need to be constructed - this is likely to have a greater effect than the works themselves.

The proposed strengthening in this report has been developed to minimise the amount of work as far as possible. This includes options with minimum material content, and options which avoid the need for heavy plant and equipment.

A designers' environmental risk register is included in Appendix E.

8 Conclusions

8.1 Summary

The viaduct supporting the Cairngorm Funicular Railway is unable to support its original design loadings in its current condition.

A strengthening scheme has been devised to address the failings. The components of the strengthening scheme are described and matched to the deficiencies as shown below:

Element	Deficiency	Strengthening solution	Strengthening extent
Main beams	Many spans are overloaded in shear Risk that all scarf joint have deficient shear strength	Strengthen all scarf joints and overloaded beams using external bars	360 joints. 166 out of 388 beam ends to 1st crossbeam (approx 40%), 20 to 2nd crossbeam (approx 5%).
	5 spans are overloaded in hog bending where cast into anchor blocks	Install new bearings at anchor blocks	5 out of 6 anchor blocks
	Severe cracking at piers which could lead to reinforcement corrosion and hence a further loss of strength in future	Reinforce all type 3 beam connections	13 insitu joint locations at 10 piers (26 repairs)
Bearings	At low temperatures some bearings will travel beyond extent of sliding surface due to misalignment	Replace all bearings - now 3 bearings per	196 existing bearings plus 97 new lateral guides.
	On all spans vertical and lateral load capacity is exceeded	pier	guides.
	Bearings are unable to resist uplift	None - Revise emergency procedures	
Piers	Crossheads are overloaded in the steepest part of viaduct	Install props wherever pier	43 out of 88 piers resulting in 46 prop locations (approx 50%)
	Columns overloaded in bending and shear on the taller piers	and/or pier crosshead is overloaded or	
	Piers have low resistance to collision load and could fail if impacted	pier is at risk of collision	
Pier foundations	Many piers are thought to have rotated due to the inclined bearing loads, but it is not thought this rotation will lead to collapse		

Table 2

Summary of deficiencies identified in the appraisal

The estimated cost of the strengthening has been determined as £5.85 million with a +/-20% margin of error.

Two programme options for the concept strengthening scheme have been explored. One would take place over two summer seasons with completion in October 2021, the other in a single season with completion in November 2020. The single season option assumes a longer construction period of early April to late November and is significantly more exposed to the risk of poor weather. Both approaches deliver the scheme to the same cost estimates.

Alternatives to strengthening exist. Options are discussed in section 3 above.

8.2 Further work

The concept strengthening scheme described in this report has been devised for cost estimating purposes only. The design needs to be developed into a detailed design prior to construction.


Changes to the emergency operating procedures are recommended to address the risk of bearing uplift. Possible actions are described in section 5.4 above.

If it is considered necessary to refine the budget price, further development could be undertaken to address the items listed in section 6.4 above.

Appendix A Testing details

Sketch - Shear testing scarf joints

.



Appendix B Technical notes

TN-03-013: Technical note on bearing articulation

TN-03-014: Technical note on feasibility of a like-for-like bearing replacement



HIGHLANDS AND ISLANDS ENTERPRISE

CAIRNGORM FUNICULAR RAILWAY

BEARING REPLACEMENT OPTIONS

A REVIEW OF ARTICULATION ARRANGEMENT

CONTENTS

1	Current bearing details	1
2	Replacement options	7
2.1	Keep bearings inclined	7
2.2	Convert to flat bearings	8
2.3	Correcting the misalignment	10
3	Recommendation	11

1 Current bearing details

Detailed drawings of the existing bearings are not available. The available information on the bearing details is limited to that shown in the original design drawings and site observations. It is believed that the bearing assemblies consist of a bottom plate, pot bearing, sliding surface, and top plate, as shown in Figure 1. Note that the presence of an elastomeric "pot" permitting rotation has not been verified but is believed to be the most likely configuration. At each pier, one bearing includes a sliding lateral guide to resist transverse loads.

The bearing assemblies have a total depth of 114 mm according to the design drawings, which is consistent with site measurements. The guide width on the guided bearings is not reported but has been scaled from drawings and photographs to be approximately 50 mm.

At the top connection, the bearings are bolted to 20 mm thick plates on the rail support beam soffit. "Tang" plates are welded to the soffit plates and embedded into the in-situ joint concrete (Figure 3 and Figure 4).

PROJECT NO	DOCUMENT NO					
A116993	TN-03-013					
VERSION	DATE OF ISSUE	DESCRIPTION	PREPARED	CHECKED	APPROVED	
V1	31-01-2019	For Information				

ADDRESS COWI UK Limited Bevis Marks House 24 Bevis Marks London EC3A 7JB

> TEL +44 207 9407 600 WWW cowi.com

At the bottom connection, the bearings are bolted to either a tapered plate or a steel bearing shoe. The bottom connection type varies with angular inclination. Piers with greater than 9.2° inclination use steel bearing shoes, whilst all others use tapered plates. The tapered plates / steel shoes are welded to dowels that extend approximately 150 mm into grouted pockets in the crosshead beams (Figure 5).

At the anchor blocks (i.e. just below the movement joints) tapered plates / steel shoes are not used as the inclination of the anchor block concrete face approximately matches that of the rail support beams. The bearings are therefore bolted to flat plates that are welded to dowels penetrating into the anchor blocks (Figure 6).

The tapered plates / steel shoes are supported on grout pads. The thickness of the grout pads varies to accommodate construction tolerances but are generally around 50 mm.






Figure 1 Current bearing detail at piers with tapered plates (tapered plates used at 62 No. locations)

CAIRNGORM FUNICULAR RAILWAY 3










Figure 3 Cross-section of rail support beam at bearing location (guided bearing shown).


COWI

4 CAIRNGORM FUNICULAR RAILWAY










COWI CAIRNGORM FUNICULAR RAILWAY









5

6 CAIRNGORM FUNICULAR RAILWAY



Figure 8 Example of guided bearing with tapered bottom plate



Figure 9

Example of free sliding bearing with bottom steel shoe



Figure 10 Example of guided bearing with bottom steel shoe

2 Replacement options

Observations of the bearings by COWI and ADAC Structures Ltd. have noted that the bearings are misaligned to original design intent (see Section 2.3). As the bearings approach their assumed design life of circa 20yrs the PTFE sliding surfaces are exhibiting significant wear. The bearings have also been calculated to be ~50% overstressed due to SLS loading at the operational wind case, using BS 5400-9.1 criteria. Bearing replacement is therefore deemed necessary, with the new bearings being modified to prevent overstress from occurring.

Two options for bearing replacement are here discussed: (1) maintaining the current bearing inclination, or (2) replacing the inclined bearings with flat bearings with sliding surfaces true to horizontal.

2.1 Keep bearings inclined

Replacing the bearings and keeping the existing inclination would have the following advantages and disadvantages.

Advantages:

Simpler to replace. Could likely keep beam soffit plates and tapered plates / steel shoes as they are. The photographs of the bearings appear to show adequate dimensions to allow for an increase in sliding surface / pot elastomer area without needing to modify the bolt spacing (a free sliding bearing diameter of 120 mm would give an SLS pressure of approximately 25 MPa and a ULS [accidental wind case] pressure of approximately 45

COWI

8 CAIRNGORM FUNICULAR RAILWAY

MPa; the guided bearing is not currently overstressed due to the normal reaction except due to the ULS accidental wind case, with an SLS pressure of approximately 32 MPa).

(Note that keeping the steel shoes assumes that they are in adequate condition. Possible observations of cracks in the shoes by ADAC Structures Ltd. may further investigation and necessitate replacement of the shoes. Replacement of the shoes would either require destructive works in the crosshead beams or site fabrication works to replace the existing hollow sections.)

Disadvantages:

Does not help with the problems relating to overload of the substructure. Further strengthening works on the substructure would be required.

2.2 Convert to flat bearings

Replacing the bearings and switching to zero inclination could involve essentially inverting the current system, with tapered plates / steel shoes now attached to the beam soffit and a flat plate system on the crosshead beams. It would have the following advantages and disadvantages.

Advantages:

Removes much or all of the problems relating to overload of the substructure. This would prevent any need to strengthen the piers or foundations.

Disadvantages:


Assuming that it is impractical to cut the tapered plates or steel shoes on site, destructive works to the crosshead beams maybe required to remove the tapered plates / steel shoes. Destructive works to the beams / in-situ joints would possibly also be required if the new inverted tapered plates / steel shoes could not be attached to the existing soffit plate.

If the superstructure is to be replaced, it may be simpler to also replace the crosshead beams when removing the tapered plates / steel shoes. The post-tensioned connection between crosshead beams and pier may make for a relatively simple replacement procedure.

An alternative option may be to install additional inversed taper plates / shoes that effectively create flat surfaces. However, this would require raising the elevation of the track to accommodate the additional taper plates / shoes, which would also necessitate modifying works at locations where the track level is fixed (anchor blocks, tunnel entrance, etc...).

Additional local axial, bending, and shear stresses may be induced in the rail support beams due to thermal expansion / contraction. The axial compression that is currently induced in the rail support beams due to dead load would no longer occur, which may lower the moment or shear capacities of certain areas of the beams.

Change in the rail level above the bearings would occur due to thermal expansion / contraction. At the anchor block bearings, this could create a prohibitive change in rail level across the movement joints (see Figure 11). A way of preventing this effect is discussed in the following Section 2.2.1.





2.2.1 Convert to flat bearings except at anchor blocks (movement joint)

This option is essentially the same as converting to flat bearings but keeping an inclined bearing at the anchor block, which removes the issue of a change in rail level across the movement joint (Figure 11).

However, this option increases the stresses that must be carried by the beams in the span immediately below each movement joint. When thermal expansion occurs, the end of the span at the movement joint will be pushed upwards by the inclined bearing, relative to the pier below. When thermal contraction occurs, the end of the span at the movement joint must deflect downwards under its self-weight to maintain contact with the inclined bearing.

Calculations were undertaken to quantify these effects, based on the assumption that the final span deflects as a cantilevered beam. Partial factors for BD 37 combination 3 were used as the stresses of concern are thermal in nature. It was found that differences in temperature of $\pm 25^{\circ}$ C would cause a maximum differential vertical movement of ± 25 mm, a maximum change in reaction at the inclined bearing of ± 7 kN, and a maximum change in moment at the pier below the movement joint of ± 120 kNm.

For the case of thermal expansion, the bending moments induced at the pier below each movement joint would be sagging (i.e. tension on the beam bottom). The beam bottom reinforcement is not continuous through the in-situ joints. Note that due to the construction method, the dead load does not create a permanent hogging moment at supports that would prevent a net sagging moment from developing under such thermal loading. Strengthening works would therefore likely be required to prevent sagging moment failure.

2.3 Correcting the misalignment


Regardless of which option is chosen, if the superstructure is to be kept, steps must be taken to correct the current bearing misalignment. The bearing misalignments measured by ADAC Structures Ltd. and extrapolated to a temperature of 5°C are given in Figure 12. A temperature of 5°C was used as this is the midpoint between the minimum (-19°C) and maximum (29°C) effective bridge temperatures, as described in the Schedule of Basic Assumptions. The misalignments are in all cases positive (i.e. reducing available space for contraction) and less than 120 mm.


If the superstructure is to remain and the bearings kept inclined, a simple way to deal with the misalignment is to use a new bearing top plate that extends to the end of the beam soffit plate, as shown in Figure 13. As the beam soffit plate is 635 mm long and the existing bearing top plates are 335 mm long, this would give an additional 150 mm available for contraction. Additional bolts could be added into site-drilled holes in the soffit plates if required.

A drawback to this method is that the misalignment between the piers and superstructure joints / diaphragms would remain. At extreme cold temperatures, the bearing centreline could be as much as 200 mm misaligned from the joint centreline. This method would also need modification to work in the passing loop where beams are terminated at diaphragms, as the 635 mm long soffit plates extend past the diaphragm width and therefore cannot support load.

Another option for dealing with the misalignment is to attempt to straighten any piers that are leaning in the uphill direction. Note that it has not definitively been determined that all bearing misalignments are due to leaning piers, and therefore further site investigations would be required to verify this before proceeding with this option. This option is not recommended due to high cost and uncertainty.

If the superstructure is to be replaced, the current bearing positions can be accounted for in the new design.








Figure 13 Option for dealing with misalignment if keeping inclined bearings – use of extended bearing top plate (with possible bolt into site-drilled hole in beam soffit plate)

3 Recommendation

The following recommendation is based on the assumption that the existing superstructure will remain. If a decision to replace the superstructure is pursued, this recommendation would have to be revisited.

Modification of the current bearing system to incorporate true to horizontal sliding surfaces would eliminate the need for substructure strengthening and also likely prevent any future misalignment due to rotation of the piers. However, these advantages are deemed to be insufficient to justify such a bearing replacement scheme for the following reasons:

COWI

- 12 CAIRNGORM FUNICULAR RAILWAY
 - The considerable destructive / fabrication site works required would likely more than negate any economic advantage due to reduced substructure strengthening. Additional strengthening works to permit sagging moment across certain piers would also likely be required (see Section 2.2.1).
 - The advantage of preventing any potential further misalignment due to pier rotation may be covered regardless, as the favoured substructure strengthening scheme involves propping of the piers. The piers scheduled for strengthening include those with the largest existing misalignment.
 - The local stresses that would be induced in a superstructure with flat bearings due to thermal movements are difficult to accurately predict using analytical methods. These stresses could result in cracking and durability issues over the long term.

It is therefore recommended that maintaining inclined bearings be pursued as the favoured option, despite the associated substructure strengthening requirements. Simple extensions to the top bearing plate can be used as a costeffective method of allowing for the existing bearing misalignment.



HIGHLANDS AND ISLANDS ENTERPRISE

CAIRNGORM FUNICULAR RAILWAY

BEARING REPLACEMENT

FEASIBILITY STUDY FOR A LIKE-FOR-LIKE REPLACEMENT

CONTENTS

1	Introduction	2
2	Design requirements	2
2.1	Loads	2
2.2	Articulation	3
2.3	Existing fixing details	4
3	Bearing supplier design review	5
4	Future recommendations for detailed design	6
5	Conclusions	7

ANNEXES

Annex A	Concept bearing schedule for a like-for-like replacement scheme
Annex B	Ekspan guided spherical bearing preliminary design drawings



ADDRESS COWI UK Limited Bevis Marks House 24 Bevis Marks London EC3A 7JB

> TEL +44 207 9407 600 www.cowi.com

1 Introduction

As part of the strengthening scheme design works, COWI worked with bearing suppliers on a feasibility study for the design of like-for-like replacement of bearings. In this context, "Like-for-like" replacement refers to maintaining the existing bearing articulation within the existing bearing footprint. A like-for-like replacement would require a bearing of larger capacity to fit into existing geometric restraints and bolt attachment positions.

The benefit to a like-for-like replacement for bearings is the elimination of intrusive works at the pier locations. Any remedial works to refurbish bearing fixings would be cumbersome, timely and thus expensive. Pursuing a solution that minimised intervention and reduced risk would benefit both budget and programme.

The preliminary bearing replacement design assumed the following:

- 1 The existing viaduct superstructure will remain, albeit with strengthening.
- 2 The existing upper and lower bearing plate will remain with the associated lower taper plate inclination as recommended in the bearing articulation review (see COWI technical note TN-03-013).
- 3 The Accidental wind case will be considered as a Eurocode Accidental Design Situation. Therefore, all ULS load partial factors are taken as 1.0 and the case is not considered at SLS (as recommended in COWI technical note TN-03-012).

2 Design requirements

2.1 Loads

A.F. Cruden Associates design drawing CA150/2/42 shows a table of "horizontal" and "vertical" bearing loads that are assumed to have formed the basis for the initial bearing design specification. It is assumed the "horizontal" and "vertical" loads correspond to the transverse horizontal force and the normal force, respectively.

These loads are considerably different from those obtained by COWI during the structural appraisal. Table 1 shows a comparison between the two sets of loads. The maximum transverse and normal forces from the design drawings are approximately 30% and 50% lower than those determined by COWI. The design drawings also show uplift as occurring at SLS, but COWI's appraisal found that there is always a compressive normal force at SLS. Both sets of loads have comparable ULS uplift forces.

The full set of loads used for COWI's concept bearing replacement design are given in the bearing schedule shown in Annex A. Note that the ULS uplift loads were not considered in the design. Instead, a minimum normal force of +20kN (compressive) was used at both SLS and ULS. This was because, despite the design drawings showing uplift forces, the existing bearings are not believed to

have any capacity to resist uplift. The existing fixing details to the rail support beams and pier crossheads also do not have the capacity to transfer uplift loads. Uplift only occurs in the upper half of the viaduct. Possible methods for dealing with uplift loads in detailed design are further discussed in Section 4.

	ULS	(kN)	SLS	(kN)
Parameter	From design drawings	From COWI appraisal	From design drawings	From COWI appraisal
Transverse force	282.4	380	157.7	230
Normal force (max)	214.9	475	177.8	375
Normal force (min)	-48.4	-65	-25.4	20

 Table 1
 Comparison of critical bearing loads from the design drawings and COWI's structural appraisal

2.2 Articulation

A.F. Cruden Associates design drawing CA150/2/42 shows a "required movement" of \pm 75mm longitudinally.

Based on critical effective bridge temperatures calculated to BD 37/01 and a coefficient of thermal expansion of 12×10^{-6} °C⁻¹, COWI determined a critical SLS (i.e. unfactored) longitudinal movement of ±95mm from a baseline temperature of +5 °C. Note that this demand only occurs at one place: the joint at the top of the longest freely articulating "area" of the viaduct (located at the movement joint on the lower side of anchor block 48). Thermal movement demands are considerably lower at many other areas of the viaduct and vary with distance away from the fixed anchor block supports.

The design of the replacement bearings also had to consider the existing bearing misalignment. Data from a survey of bearing positions by ADAC Structures Ltd. was analysed to determine theoretical bearing misalignments at +5 °C. The maximum misalignment at +5 °C is 112mm. However, this misalignment does not coincide with the location of maximum thermal movements. Pier 44 was found to have the maximum combined misalignment plus thermal movement (approximately 180mm). A misalignment of 85mm (180mm total minus 95mm thermal) was therefore considered in the replacement bearing design. (Note that the misalignment generally only increases the articulation demands associated with contraction of the superstructure.)

Critical rotations were taken from the global line beam analysis, further discussed in the appraisal report.

The full set of articulation demands used in the concept bearing replacement design are given in the bearing schedule shown in Annex A. Note that

4

misalignment was treated as an "irreversible translation" and not factored at ULS. Critical SLS (unfactored) thermal movements were multiplied by a factor of 1.3 to obtain the ULS thermal movements.

2.3 Existing fixing details

The primary reason for maintaining the inclination of the existing bearings in the concept replacement bearing design is the high cost of works associated with modifying the bearing fixings. The existing fixing details were therefore included as a constraint on the concept design.

The existing fixing details are summarised in Figure 1 and Figure 2. These are indicative and merely shows the typical bolt spacing of upper and lower plates Note that the base plate configuration shown is replaced by a built-up hollow section bearing shoe at some piers, but the bolted connection details remain the same. The key constraints are as follows:

- The existing beam soffit plate and base plate are a minimum of 20mm thick. It is assumed the existing plate receives an M16 bolt in blind holes; the same diameter as the existing bolts. Given the considerably higher loads in the replacement bearing design compared with the original design, additional bolts were required to be permitted in the replacement bearing design.
- The existing base plate has four M16 bolts at 180mm square. Additional bolts can be added to site-drilled threaded holes, but the new bolt pattern must remain within the 180mm square area. Wider bolt spacing would either interfere with the hollow sections (at the locations with bearing shoes) or prevent the minimum edge distance from being achieved.
- The existing beam soffit plate is 635mm long. The new bearing top plate and sliding surface must fit within this length while still allowing for the full translation demand due to misalignment plus thermal movements.




Figure 1 Sketch highlighting typical fixing dimension details – longitudinal section

(YWI CAIRNGORM FUNICULAR RAILWAY




Figure 2 Sketch highlighting typical fixing dimension details - transverse section

The full set of fixing criteria used in the concept bearing replacement design are given in the bearing schedule shown in Annex A.

3 Bearing supplier design review

Two bearing suppliers were provided with the preliminary bearing schedule and requested to investigate the feasibility of a like-for-like bearing replacement scheme. Both suppliers determined that a replacement free sliding bearing could meet the design criteria, albeit with uplift ignored. However, both suppliers were unable to design a satisfactory replacement guided bearing. Design options for the guide bearing that were investigated included:

- A pot bearing + sliding surface + guide assembly (i.e. similar to the existing > guided bearing)
- > A link bearing (trunnion type) + sliding surface assembly
- > A spherical bearing + sliding surface + guide assembly

The spherical guide bearing assembly designed by Ekspan was perhaps the closest to achieving the design criteria. Preliminary drawings of this bearing design are given in Annex B.

The primary issues preventing any of the guided bearing options from meeting the design criteria were as follows:

- A link bearing system was unable to fit within the overall height criteria > (114mm)
- > The maximum horizontal (transverse) load, in conjunction with the minimum normal compressive load, necessitated a considerably larger

5

6 CAIRNGORM FUNICULAR RAILWAY

diameter pot/spherical bearing and sliding surface than is used on the existing guide bearing. This created two problems:

- > There was no clearance for the baseplate bolts to fit within the 180x180mm available area.
- > The sliding surface could not remain within the available 635mm beam soffit plate length at the ULS translation demand.

The geometric constraints, although not present at all locations, resulted in both bearing suppliers being unable to achieve a like-for-like replacement for the guide bearing. The constraint of the base plate 180x180mm bolt fixings proved the most prohibitive problem.

4 Future recommendations for detailed design

A suitable like-for-like guide bearing design that would work for all piers could not be identified. However, the design criteria corresponded to the worst-case loads and translations of any guide bearing in the viaduct. In reality, the force and translation demands vary considerably along the length of the viaduct. It may be possible to use a like-for-like two-bearing replacement scheme at many of the piers by considering a pier-by-pier breakdown of demands during detailed design. The following factors are particularly likely to have a beneficial effect:

- Lower regions of the viaduct are subjected to lower wind speeds and therefore lower transverse forces and higher minimum normal forces. It is possible that a smaller diameter spherical (or pot) bearing could be used in these locations, potentially allowing the baseplate bolt configuration to fit within the available 180x180mm area.
- Regions of the viaduct that are close to an anchor block will exhibit smaller longitudinal thermal movements. Many piers also have limited misalignment. It is therefore apparent that the required upper sliding surface could easily fit within the existing 635mm beam soffit plate length in many cases.

Uplift was not considered in the concept bearing design as the existing fixings have no capacity to resist uplift. Consideration must be given to uplift in the detailed design. It is noted that uplift only occurs in the Accidental wind case (i.e. with a broken-down carriage clamped to the rails during a storm). Works to modify the existing bearing fixings to transmit uplift would likely be prohibitively expensive. Three alternate options for dealing with uplift during detailed design are presented here:

1 Allow uplift to occur. Bearing separation is undesirable, but given that it is only expected to occur in an extremely rare load case, it may be permissible to accept. If this option is pursued, detailed design would have to verify that the occurrence of uplift would not lead to instability or overstress in other areas of the structure.

- 2 If the Client is willing to accept additional residual risk, remove the Accidental wind case from the design basis entirely. (Note that this option would also reduce the maximum transverse loads and possibly permit a like-for-like replacement at more or all piers.)
- 3 Adapt the existing operating procedures in the event of a carriage breakdown that involves either:
 - > clamping the superstructure to the pier to prevent uplift, or
 - adding additional kentledge to the carriage to prevent uplift. (Note that this would require on the order of 15 tonnes kentledge.)

5 Conclusions

Bearing design is governed by the combination of low vertical load and high lateral load. Using a single worst-case design bearing specification it has not been possible to confirm a like-for-like bearing replacement scheme is a viable option. However, given the wide variability of load combinations along the length of the viaduct, further detailed design may permit optimization of bearing types for a replacement scheme, thus reducing costs and programme.

Uplift is only critical in the upper half of the viaduct. Uplift could be resisted by additional strengthening and thus costs for preventative measures or HIE may wish to consider management of residual risk in operational management procedures. Further consideration to address uplift concerns are required during future detailed design.

COWI

8 CAIRNGORM FUNICULAR RAILWAY

Annex A Concept bearing schedule for a like-for-like replacement scheme



Bevis Marks House 24 Bevis Marks London EC3A 7JB

Caimgorn Funicular Railway Replacement Bearing Schedule

				Like-for-like	replacement
Symbolic representation	t of bearing fun	ctions (BS EN 1337	-1 Table 1)	+	4-1->
Bearing type (BS EN 13	37-1 Table 1)			2.3	2.2
lo, required				99	97
eating Material	Upper Surface			Existing steel plate	Existing steel plate
	Lower Surface			Existing steel plate	Existing steel plate
llowable Average	Upper Face	SLS			
ontact Pressure		ULS			
(/mm2)	Lower Face	SLS			
	100000000000000000000000000000000000000	ULS			
	Upp	er Face	Transverse	340 max.	340 max,
			Longitudinal	635 max.	635 max.
lear Surface	Low	er Face	Transverse		
Imensions (mm)			Longitudinal		
000000000000000000000000000000000000000		Pot	Transverse		
			Longitudinal		
upport Area (minima)	Upper Surface	Longitudinal (mm) (along bridge direction)	635	635
			(across bridge direction)	340	340
		Connection to su		Tang plates cast into in-situ stitch joints	Tang plates cast into in-situ stitch joint
	Lower Surface	and the second design of the s	n) (along bridge direction)	260 (300 where bearing shoes are used)	260 (300 where bearing shoes are use
			(across bridge direction)	260 (300 where bearing shoes are used) 260 (300 where bearing shoes are used)	260 (300 where bearing shoes are use
		Connection to sul		Doweled to crosshead beams	Downled to crosshead beams
feximum bearing			height (mm)	114 (to match existing)	114 (to match existing)
imensions (mm)	Upper surface		Transverse	340 (existing bolt holes at 260)	340 (existing bolt holes at 260)
	oppor surnes		Longitudinal	635 (existing bolt holes at 260)	635 (existing bolt holes at 260)
	Lower surface			260 (existing bolt holes at 180)	260 (existing bolt holes at 180)
	Lower suitace		Transverse Longitudinal	260 (existing bolt holes at 180)	260 (existing bolt holes at 180)
pe Of Fixing Required		T	Upper Face	Bolt to M16 threaded holes	Bolt to M16 threaded holes
pe of Poing Required			Lower Face	Bolt to M16 threaded holes	Bolt to M16 threaded holes
					and the second s
Design Load Effects (kN)	SLS	Normal	Max.	375	375
(404)			Permanent	80 (40 where beams are non-continuous)	80 (40 where beams are non-continuou
			Min	20	20
		Transverse		n/a	230
			In direction of local Inclination)	n/a	n/a
	ULS	Normal		475	475
		Uplift	- 1	-65	-65
		Transverse		n/a	380
			In direction of local Inclination)	n/a	n/a
	SLS	Min. normal		n/a	20
	combination	Max coincident tr	ansverse	n/a	230
	ULS	Min, normal		n/a	-65
	combination	Max coincident to	procession and a second s	n/a	340
Translation (mm)	SLS	Irreversible	Transverse		•
			Longitudinal	-85, +10	-85, +10
	0	Reversible	Transverse		
		-	Longitudinal	±95	±95
	ULS	Irreversible	Transverse		
			Longitudinal	-85, +10	-85, +10
		Reversible	Transverse		
			Longitudinal	±125	±125
Rotation (radians)	SLS	Irreversible	Transverse		
	1000		Longitudinal		
		Reversible	Transverse		
			Longitudinal	±0,006	±0.006
	ULS	Irreversible	Transverse	•	•
			Longitudinal		•
		Reversible	Transverse		
		and a second second second	Longitudinal	±0.008	±0.008
			Transverse		
	Maximum rate	e (radians/100kN)	Longitudinal		
Tolerable movement	of bearing unde	r transient loads	Vertical	small	small
	(mm)		Transverse	-	smell
	000000		Longitudinal		-
			Transverse	1	
Allowable resistance to	translation und	ier SLS loads (kN)	Longitudinal		
			No. of Concession, Name		
Allowable resistance to	rotation under	SLS Loads (KNm)	Transverse		
			Longitudinal		

Notes:

Notes: 1. Sign convention for longitudinal translation is as follows: negative refers to deformation associated with expansion of the superstructure, 2. Sign convention for longitudinal translation is as follows: negative refers to deformation associated with expansion of the superstructure, 2. Sign convention for longitudinal translation is a propendicular to the the of track, i.e., rotation associated with hogging or anging of the superstructure, 3. It is assumed the core bearing will consist of a pot bearing and sking eurinous associated with inoging or angenesit. 4. Top and bottom adding bearing fields are currently missigned with one another by up to -135mm or +256mm at a reference temperature of 5°C. This missignment has been lonk-ded as an inevenible deformation in the design displacements. 8. It is assumed that all incremition deformations deformation (e.g. creep) have already occurred and therefore need not be accounted for in design of the neglecoment bearings. 6. Provisions shall be made for all new bearings to be areplaceable.

COWI ref: Drawing Ref: Revision: Date:

A116993 r/a preliminary 01-Mar-19

.

Annex B Ekspan guided spherical bearing preliminary design drawings

	_		_		
-	-	-	-	-	-

A

В

С

D

E

F


1

2

3

4


CUSTOMER / PROJECT DETAIL	s				155	UE / CHA	INGES	()
	3			ISSUE	DESCR	IPTION	DATE	AUTHORITY
CLIENT / CUSTOMER				STATUS	PRELIMIN		19/03/19	-
	COWI			2	PRELIMINA	RY ISSUE,	22/03/20	
PROJECT / STRUCTURE	CAIRNGORM	OUNTAIN RAILW	AY		TRANSL		19	
PRODUCT POSITION REFERENCE IF APPLICABLE}	GUIDE							
CLIENT / CUSTOMER DRAWING NO IF APPLICABLE)	D. A116993							
PRODUCT DETAILS								
YPE	EN 1337 - 7 SPH	ERICAL BEARING		1				
DESCRIPTION	SPHERICAL BEA 11GE0050-250	RING, GUIDE (500)kN) -	1				
KSPAN DRAWING NO.	-]				
EKSPAN CALCULATION NO. IF APPLICABLE)	15508-GD-C01							
DESIGN PARAMETERS - LOADI	NG			1				
	SLS (KN)	ULS (KN)						
MAX VERTICAL LOAD, Nmax	375	4	75					
PERMANENT VERTICAL LOAD, Not	<i>erm</i> 40		4					
MIN VERTICAL LOAD, Nmin	20	2	20					
MAX TRANSVERSE LOAD, Vy	230	3	80					
MAX LONGITUDINAL LOAD, Vx								
MAX COMBINED LOAD, Vr	-		-					
DESIGN PARAMETERS - MOVE	MENT							
	SLS +/- (mm)	ULS +/- (m	m)					
MAX TRANSVERSE MOVEMENT, vy IRREVERSIBLE + REVERSIBLE)	-		-					
MAX LONGITUDINAL MOVEMENT, IRREVERSIBLE + REVERSIBLE)	<i>Vx</i> 180	2	10		METRIC / DI			FW
	SLS +/- (Rad)	ULS +/- (Rc	ad)					
MAX TRANSVERSE ROTATION, ay	-		-			/	-00-	-
MAX LONGITUDINAL ROTATION, a	1× _		-			-	/	
MAX TRANSVERSE ROTATION, ay	-		-					
MAX LONGITUDINAL ROTATION, a	¹ × 0.006	0.0	800]		٨		
				E	KSP	AN N	EKSPAN COMPAS 410 BRIG SHEFFIE S9 2SP	S WORKS HTSIDE LANE
	10000		~	THIS DOCU WHICH MA USED OR P	MENT CONTAINS P Y NOT, WITHOUT TH PRODUCED IN WH DT EMPLOYED BY E	ROPRIETARY AND TE PRIOR WRITTEN TOLE OR IN PAPT	CONFIDENTIAL IN CONSENT OF TO OR COMMUNICA	IFORMATION EKSPAN LTD, BE TED TO ANY
DRAWN		ORIGINAL DRAWIN	G	PERSON NO		0.00000000		ISSUE
DATE	22nd MAR 2019		MAR 2019			WING IBER SINAL 1:10	15508-GD-0	2 2





Appendix C Strengthening scheme details


Sketches:


SK01 rev A	Substructure - pier propping
SK05 rev A	Bearings
SK11	Type 3 beams - continuity
SK12	Anchor blocks 0, 65 and 78
SK13	Anchor blocks 14 & 29
SK14	External shear reinforcement at scarf joints
SK15	External shear reinforcement at first crossbeam

















Appendix D Strengthening scheme extents

Tabulated chart of locations to be strengthened


Graphical view of deck strengthening

Graphical view of pier strengthening

	Are type 3 connections to be strengthened? Sketch reference Mumber of type 3 connections per pier Reason = Improve durability by reducing cracking																													
	ο Sketch reference Ο																													
	Are type 3 connections to be																													
	Reason = Beam overloaded in shear	>		`			5	>	\$	>							>		>	\$	>	>	>	>	>	5	>	5	s	\$
	No of beams strengthened at 2nd crossbeam in span above																													
	No of beams strengthened at 2nd crossbeam in span below																													
	No of beams strengthered at 1st crossbeam in span above	ſ	1 14			1	2	2	2								~	1	1 10	2	2	2	N	2	7	2	2	2	2	~
	No of beams strengthened at 1st crossbeam in span below			2					2										2				2					2		2
	Sketch reference	CV1E	SK15	SK15		1	SK15	SK15	SK15	SK15							SK15	CK15	SK15	SK15	SK15	SK15	SK15	SK15	SK15	SK15	SK15	SK15	SK15	SK15
	nb to Suq crosspesm? Is the span above to be strengthened up to Sud crosspesm? Is the span below to be strengthened																													
	Is the span above to be strengthened at	Voc	Yes				Yes	Yes	Yes								Yes	Vac	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
	Is the span below to be strengthened at		Yes	Yes				Yes	Yes	Yes									Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
	nietrocru dtgroert2 = nose9		>	>	\$	×-	5	>	\$	>	>	>	×	>	>		,	5	>	>	2	>	۲	>	>	>	>	1	> !:	>
1	Number of Joints per pier		4	4	4	4	4	4	4	4	4	4	4	4	4		•	• •	4	4	4	4	4	4	4	4	4	4	4	4
24	Sketch reference <u>v</u>		SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14		2112	CKIA	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14	SK14
c	Are the scarf joints to be strengthened? Sketch reference Mumber of joints per pier Reason = Strength uncertain Is the span above to be strengthened at fits the span above to be strengthened at is the span above to be strengthened at fits the span above to be strengthened at the fits the span above to be strengthened at the fits the span above to be strengthened at the fits the span above to be strengthened at the span above to be strengthened at the fits the span above to be strengthened at the span above to be span above to be span above to be strengthened at the span above to be span above to be span above to be span above to be strengthened at the span above to be span above to b		Yes	Yes	Yes S		Yes	Yes	Yes	Yes	Yes S	Yes			Yes		200			Yes	Yes	Yes	Yes	Yes 9	Yes	Yes				Yes
	bangilesim gainsad gaitisix3 = noseaя																	Ì												
	bebsoner = Existing bearings overloaded		>	\$	\$	>	5	s	\$	\$	\$	>	s	>		×	,	5	>	\$	>	5	`	•	`	5	>	5	*	• •
	Number of lateral load bearings per pier		-11	۳	-	-	-1	-	-	-	-	-	1	-	-	-		• •	-	+	-	1	1	÷	-	-	-	-1	-	
	pier Number of vertical load bearings per		2	2	2	2							7	2	~	м	r													2 2
	Are besiden of to be replaced and a a b c c c c c c c c c c		SK05/A		SK05/A						SK05/A	SK05/A	SK05/A	SK05/A		SK05/A	CUDEIA			SK05/A		SK05/A		SK05/A						SK05/A
ć	g Ā fboostger ed of sprinsed enA		Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Vae	Yee	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
	Shenartipriate and thork book to be strengthenarts at the anchor block to be strengthenergy and the strengthenergy	2	4														, T													
1	Sketch reference	CK12	20													- 11	SK13													
	Is the anchor block to be strengthened?	Vac	2													100	Yes													
	Reason = Collision risk			>	\$																									
	bangilazim gninsad gnitzix3 = noseaЯ																													
.9	Reason = Crosshead overload																													
tent	beohavo nmuloD = noseas																													
vay g ex	Number of props per pier			2	2																									
n Railv thenin	v Sketich reference			SK01/A	SK01/A																									
ountail	ני ג'הפי ג'ס be propped? ע			Yes	Yes																									
A116993 Cairngorm Mountain Railway Summary of strengthening extents		Area Pier number	1	8	m	4	s	9	1	80	6	10	11	12	13	14	14 Anchor	16	17	18	19	20	21	22	23	24	25	26	27	28
A116993 Cairngori Summary		D Ar	5														14.													
A1 Ca		4 Area	4														7													1


pler to be propped?					Ancho	Anchor blocks		Bearings				Bea	m she	ear si	treng	E	бu							Typ	Type 3 connections	onne	ctio
q ərti zī	Number of props per pier	Reason = Column overload Reason = Crosshead overload	Reason = Collision risk Reason = Collision risk		Is the anchor block to be strengthened?	Sketch reference Reason = Beam overloaded in hog	Sbeasings of of senineed enA	Sketch reference	pier Number of vertical load bearings per	Number of lateral load bearings per pler Reason = Existing bearings overloaded	bangilesim grinsed grinsisa = nosesy	Sbeneritignents of ot string the scent of A	Sketch reference	Number of Joints per pler	nistreonu ritionaria = nosean	Is the span below to be strengthened at Ist crossbeam?	Is the span above to be strengthened at tet crossbeam? Is the span below to be strengthened polow to 2nd crossbeam? Is the span above to be strengthened	fmeederoro bnS of qu	Sketch reference No of beams strengthened at 1.st	crossbeam in span below No of beams strengthened at 1st	crossbeam in span below No of beams strengthened at 2nd Crossbeam in span above	Crossbeam in span above Crossbeams strengthened at 2nd Crossbeam in span above	Reason = Beam overloaded in shear	Are type 3 connections to be strengthened?	Sketch reference	Number of type 3 connections per pier	Reason = Improve durability by
Area Pier number 3 29 Anchor					Yes SI	SK13 /											Yes	N,	SK15	2			,				
30							Yes	SK05/A	2	ч ,		Yes	SK14	4	2		2	i	1								
31							Yes		7	-		Yes	SK14	4	*												
32							Yes	SK05/A				Yes	SK14	4 4	\$ 5												
34 Yes SK01/A	2	•	\$				Yes			• •	>	Yes	SK14	4	•												
35 Yes SK01/A			,				Yes			1	1	Yes		4	5	-	Yes	Sk	SK15	~	-		•				
Yes			`				Yes			1		Yes	SK14	4	*		Yes	SK					`				
37 Yes SK01/A	/A 2		• •				Yes	SK05/A	~ ~	×	• •	Yes	SK14	4 4	• •		Yes	is a	SK15	2 0	208 1		• •				
Kes Yes				1			Yes					Yes		4		Kes /	Se v	n ở									
Yes			`				Yes			1	•	Yes		4	*		Yes	š					`				
41 Yes SK01/A			,				Yes	SK05/A		1		Yes	SK14	4	>	Yes Y	Yes	Ś					,				
Yes			`				Yes			-	>	Yes	SK14	4	`		Yes	Ś					•				
43 Yes SK01/A	~ ~	,	• •				Yes	SK05/A			• •	Yes	SK14	4 4		Yes	Yes	in i	SK15		-		• •				
	2						Yes			• •		Yes	SK14	4			Yes	h ở									
Yes	2	`	`				Yes			1	\$	Yes	SK14	4	>			NS.					`	Yes	SK11	2	
47							Yes		2			Yes	SK14	4	>		Yes	S	SK15	2			•	Yes	SK11		
48							Yes	SK05/A		~																	- 1
48 Anchor 49							Yec	SK05/A		` •		Vac	SK14	4	>									Vac	CK11	•	
505							Yes		1.0	1		Yes	SK14	4	>				1					Yac	CK11		
51 Yes SK01/A	IA 2 .		>				Yes				>	Yes	SK14	4	`	-	Yes Ye	Yes SK	SK15	14		2	`	Yes	SK11		
52 Yes SK01/A	(A 2		,				Yes		3	1 1		Yes	SK14	4	>		Yes	Yes SK	SK15	2 3	2	m	•	Yes	SK11	1	
Yes	4	、	`				Yes		4	2		Yes	SK14		>		Yes Yes	Ś					>	Yes	SK11	Ŧ	
Yes	4		\$				Yes	SK05/A	4			Yes	SK14	5548 	>								>				
55 Yes SK01/A 56 Yes SK01/A	4 r	\$	• •				Yes	SK05/A	4 · r	× ×	• •	Yes	SK14 SK14	9 9	• •	Yes Y	Yes Vec Ve	Yes SK	SK15	4 r n n		m r	• •	Vac	CV11	•	
Yes	1 14	\$,				Yes	SK05/A	5 10		\$	Yes		4	\$		Yes			2 1	2 1	4	>	3			
Yes	2						Yes		2			Yes		4	"			Sk		2			`				
Yes	2	`	`				Yes		2	1	\$	Yes	SK14	4	>												
Yes	2	,	5				Yes					Yes	SK14	4	*												
61 Yes SK01/A	~ ~						Yes	SK05/A				Yes	SK14	* *													
8							Yes		5	· >		Yes	SK14	* *	• •												
64							Yes			1 1	\$	Yes		4	`	-	Yes	Sk	SK15	2			>				

 = Column overload = Crosshead overload = Existing bearing misaligned = Collision risk = Beam overloaded in hog = Beam overloaded in hog 	p	Beam shear strengthening	engthening ង ដ	Ε.	Type 3 connections
nozes98 Reason Seetch Sect Reason Reason	Number of vertical load bearings per pier Number of lateral load bearings per pi Easton = Existing bearing vertioaded Reason = Existing bearing misaligned	Are the scart Joints to be strengthened Sketch reference Number of Joints per pier	Sketch reference Is the span blow to be strengthened Is the span above to be strengthened Is the span blow to be strengthened Is the strengthened Is the span blow to be strengthened Is the stren	No of beams strengthened at 1st crossbeam in span below No of beams strengthened at 1st crossbeam in span above crossbeam in span above crossbeam in span above strengthened at 2nd searn strengthened at 2nd searn strengthened at 2nd strengthened at 2nd crossbeam in span above strengthened in shear	Are type 3 connections to be strengthened? Number of type 3 connections per pler Reason = Improve durability by reducing cracking
Yes SK12 /					
		Yes SK14 4			
Yes SK05/A	2	Yes SK14 4			
	2 1	Yes SK14 4			
	2 1	SK14	,		
	н о н	SK14			
Yes SK05/A	~ ~	SK14			
		Yes SK14 4			
	1 0	SK14	,		
	2	SK14			
Yes SK05/A	2	Yes SK14 4	`		
Yes SK05/A		Yes SK14 4	Yes SK15	2	
Yes SK05/A					
Yes SK12 V					
Yes	2		×		
•	2	Yes SK14 4			
		Yes SK14 4	*		
	2				
	2	Yes SK14 4			
	7	Yes SK14 4	•		
		Yes SK14 4			
		Yes SK14 4			
		Yes SK14 4			
	2 1	Yes SK14 4			
		Yes SK14 4	\$		
Yes SK05/A		Yes SK14 4			
	A 2 1 V V	Yes SK14 4			
Yes SK05/A		Yes SK14 4	•		
		Yes SK14 4	Yes SK15	2 2	
Yes SK05/A					




This drusten is copyright of A.F.Cruden Association

Develop No. 1 OF 7 Develop No. 1 OF 7 Develop No. 1 LONGFUDINAL SECTION 1 OF 7 DAVISO/2/11 CHAINAGE 0 - 340




This drowing is copyright of A.F.Cruden Associates


Downer Division Section 2 of 7 CA150/2/12 CHANNAGE 360 - 700 2 of 7 CA150/2/12



This drawing is copyright of A.F.Cruden Associates


CONSTITUTIONAL SECTION 3 OF 7 CA150/2/13 CHAINAGE 700 - 1040






This drowing is copyright of A.F.Cruden Association








BLUE SHADING - PIERS WITH BEARINGS MISALIGNED >50mm PURPLE SHADING - PIER CROSSHEAD OVERLOADED YELLOW SHADING - ADJACENT TO ACCESS ROAD

ORANGE OUTLINE - STRENGTHENING RECOMMENDED SINCE PIER UTILISATION VERY HIGH BLUE OUTLINE - STRENGTHENING RECOMMENDED SINCE BEARINGS MISALIGNED AND PIER UTILISATION HIGH GREEN OUTLINE - STRENGTHENING RECOMMENDED TO GIVE RESILIENCE TO COLLISION LOAD RED OUTLINE - REQUIRES STRENGTHENING DUE TO PIER UTILISATION >1.00 PURPLE OUTLINE - REQUIRES STRENGTHENING TO SUPPORT CROSSHEAD

Note: BASED ON UNFACTORED ACCIDENTAL DESIGN SITUATION.

PURPLE 0 RED 2 ORANGE 0 BLUE 11 GREEN 2 TOTAL 15 R.Conton Associates

FOTAL THIS PAGE



Appendix E Health, Safety and Environment

Design decision log

Designers' health and safety risk register

Designers' environmental risk register



DESIGN DECISION LOG

Prepa	red By:	Date:	Checked By:	Date:	Approved By:	Date:
		14/2/19 update 7/3/19 12/3/19 4/4/19	d 9 9	21/2/19 09/04/19		14/04/19
Ref	Ву	Date		Design Dec	ision	
DDL1	cowi	14/2/19	Strengthening will be unde appraisal to <i>highway bridge</i> strengthened to pass <i>Euro</i> case of a stranded carriage <i>Accidental Design Situation</i>	e assessment sta code bridge desig e in storm winds v	ndards will be re-appra on standards. The accid will be treated as a Euro	lised or dental load
DDL2	cowi	14/2/19	Strengthening will also be strictly pass the appraisal, strengthening design and t checker will require additio	but almost fail. The reduce the risk	his is done to rationalise that a category 3 indep	e the
DDL3	cowi	14/2/19 updated 7/3/19	 prop. This largely e overturning. Jacketing - Enclos jacket to increase 	e the existing pier bending strength isk of future beari oping. This solution	ation and an inclined pr future bearing misalign r in new offset reinforce and to reduce uplift on ng misalignment and pi on is more modular in na ntrusive intervention inter	efabricated ment and pie d concrete foundations. er ature, o the existing
DDL4	cowi	14/2/19	Pier strengthening will also misaligned and hence it is potential future movement	suspected that th		
DDL5	cowi	14/2/19	Pier strengthening will also access track and hence ma			cent to the
DDL6	cowi	14/2/19 updated 4/4/19	sliding bearing.	r as existing - one involving 3 bearir 2 vertical load be ncept design is 3 not be made to v	bearings. Currently it is	I load only believed the

COWI UK UK-0002-1211.8 Design Decision Log

COWI

Ref	By	Date	Design Decision
DDL7	COWI	14/2/19 updated 7/3/19	 Selected beams will be strengthened in shear at around the 1st crossbeam by one of the following: Prestress - an inclined bar relieves shear from the end of the beam, External shear reinforcement - threaded bars outside the beam, New shear reinforcement - new shear links within concrete, Fibre Reinforced Polymer (FRP) wrapping - install new bands of FRP. After commentary from CMSL operatives, HIE and BAM the selected option is strengthening by external shear reinforcement. This solution; is modular in nature, requires no intrusive intervention into the existing structure, reduces risk of unknown as-built conditions, permits future inspection and maintenance at a later date.
DDL8	cowi	14/2/19 updated 7/3/19	 All beam scarf joints will be strengthened as there is uncertainty about the strength of the joint - its strength cannot be proven. This will comprise either: Safeguarding by extended bearing plate - This might not prevent shear cracking but should prevent cracking developing to full shear failure, Strengthening by one of the methods in DDL7 above. After discussion with HIE and their risk approach, the selected option is strengthening by external shear reinforcement.
DDL9	COWI	14/2/19	All piers where type 3 beams are connected will be strengthened so that the 25 diameter bars are continuous. This should reduce hog cracking in future.
DDL10	cowi	14/2/19 updated 12/3/19	 Beam ends cast into anchor blocks will be strengthened by one of the following: extend the hog bars extending from the main beams by coupling them to bars drilled and anchored into the main base, reduce hog moment by providing new soft bearing on the main base or a frame attached to the main base in front of the cast in connection. The intrusive nature of the first option is undesirable. The selected option is to provide new soft bearings.



COWI UK UK-0002-1211.4 Designers Health and Safety Risk Register

DESIGNERS HEALTH AND SAFETY RISK REGISTER

Project Name:	Cairngorm M	Cairngorm Mountain Raitway – Concept Design Development	pment	Project Nos:	Project Nos: A116993-002				
Revision Number:	umber:	Prepared By:	Date:	Checked By:	Date:	Approved By:	Date:	Notification of Risk to Stakeholders:	Date:
۲		I	14/2/19		17/3/19	I	14/04/19	Comments and copy of this register included in concept design report to the client	16/04/19
N		1	08/5/19	1	31/05/19	I	07/06/19	Updated copy included in revised concept design report to the client	07/06/19

Hazard Type:	Hazard Type: 0 – Occupational Health	C – Construction	tion	F - Functional (End Use / Demolition)	molition)
Consequence Factor	Consequence 1. No injury or illness caused Factor	Minor injury or illness resulting in less than one shift lost time	 Medium injury or illness resulting in less 4. Major injury or illness resulting in more 5. Fatality than one month lost time 	Major injury or illness resulting in more than one month of lost time	5. Fatality
Likelihood	 Never to very low likelihood of occurrence during the course of the project for design life of Scheme 	Very unlikely to occur during the course of the project or design life of the Scheme	Unlikely to occur during the course of the project or design life of Scheme	Likely to occur during the course of the project or design life of Scheme	5. Very likely to occur during the course of the project or design life of Scheme

ELEMEN	ELEMENT OF WORKS		HAZARD LOG					RISK ASSESSMENT			
DDL Ref		Haz Ref No	Description	Type	Consequence	Likelihood	Risk	Mitigative Action Rqd; Party Best Able To Manage Risk	Consequence	Likelihood	Alarp Risk
0011	Strengthening generally	HAZ1	Structure overloaded due to environmental conditions being more severe than design load cases	L.	5 - Fatality	2 - Very unlikely	0	DESIGNER - Address same load cases as original design, but with Eurocode interpretation of accidential design situation, which does not endanger any people. Verify that storm wind speed is realistic. Agree design load cases with regulator. OPERATOR - Management of the funicular to an approved operating manual. Close railway when operating conditions exceeded. Inspect before re-opening.	5 - Fatality	1 - Very low Itkelihood	w
DDL1	Strengthening generally	HAZ2	Working in mountain environment - hypothermia due to low temperatures and wind chill	oic	5 - Fatality	3 - Unlikely	5	CLIENT - Allow strengthening in summer and allow extra time to make up for lost days. CONTRACTOR - Close site when necessary. Provide adequate welfare facilities and protective clothing for the anticipated environmental conditions. DESIGNER - Design to allow off-site fabrication as far as possible.	5 - Fatality	2 - Very unlikely	ę
DDL1	Strengthening generally	HAZ3a	Being struck by train, or entangled in machinery	U	5 - Fatality	2 - Very unlikely	10	CLIENT & CONTRACTOR - If railway is to be used during construction period, then agree working and warning procedures.	5 - Fatality	1 - Very Iow liketihood	a
DDL1	Strengthening generally	HAZ3b	Being struck by rail mounted trolley.	o	5 - Fatality	4 - Likely to occur	20	CONTRACTOR - If rail mounted trolleys are to be used, then use a trolley design with low risk of run-away downhill and also use	5 - Fatality	2 - Very unlikely	10

COWI UK 0002-1211.4 COWI UK Designers Health and Safety Risk Register

Uncontrolled when Printed

Page 1 of 2

COWI

COWI UK UK-0002-1211.4 Designers Health and Safety Risk Register

ELEME	ELEMENT OF WORKS		HAZARD LOG					RISK ASSESSMENT			
DDL Ref	4	Haz Ref No	Description	Type	Consequence	Likelihood	Risk	Mitigative Action Rqd; Party Best Able To Manage Risk	Consequence	Likelihood	Alarp Risk
								positive stops on rails able to halt a run- away trolley. Agree working and warning procedures for trolley movements.			
DDL3	Pier Propping - Use of precast elements	HAZ4	Crushing hazard from heavy precast elements	U	5 - Fatality	2 - Very unlikely	10	CLIENT - Allow temporary access roads and use of appropriate plant to deliver and install items safely.	5 - Fatality	1 - Very low likelihood	Q
DDL5	Pier Strengthening for collision	HAZ5	Collapse due to construction plant colliding with structure	U	5 - Fatality	2 - Very unlikely 10	10	CONTRACTOR- Phase pier strengthening of vulnerable piers early in project.	5 - Fatality	1 - Very low likelihood	5
DDL7	Shear strengthening of beams	HAZ6	Structure overloaded due to construction loads	U	5 - Fatality	3 - Unlikely	15	CONTRACTOR, DESIGNER- Allowable temporary loading prior to strengthening to be agreed with designer.	5 - Fatality	2 - Very unlikely 10	10

Note: Not included risks due prestress, jacking, hydro demolition, drilling or ordinary reinforced concrete hazards, as these are typical construction hazards which a competent Contractor should be able to manage.



COWI UK UK-0002-1211.5 Designers Environmental Risk Register

DESIGNER'S ENVIRONMENTAL RISK REGISTER

Revision	Revision Number:	-	Prepared By:	Date:		Checked By:	Date:		Approved By:	Date:	Notification of Risk to Stakeholders:	to Stakeholders:	Date:
	Ŧ		I	14/2/19		I	17/03/19		11	11/04/19	Comments and copy of this register included in concept design report to the client	of this register lesign report to	16/04/19
Hazard Type:		0 - Occupational Health			0	C - Construction			F – Function	nal (End U	F – Functional (End Use / Demolition)		
Consequence Factor		1. No environmental impact	2.	Limited impact o immediate area)	Limited impact on local scale (i.e. site or immediate area)	ń	Limited impact on wider scale or moderate impact on local scale	cale or scale	 Moderate impact on wider scale or high impact on local scale 	der scale (ç,	High impact on wider scale	
Likelihood	÷	Never to very low likelihood of occurrence during the course of project for design life of Scheme	of the 2.	Very unlikely to of the project or Scheme	Very unlikely to occur during the cou of the project or design life of the Scheme	course 3.	Unlikely to occur during the course of the project or design life of Scheme	if Scheme	 Likely to occur during the course of the project or design life of Scheme 	le course (Scheme	ŝ	Very likely to accur during the course of the project or design life of Scheme	e course of cheme
ELEMENT	ELEMENT OF WORKS		HAZARD LOG						RISK ASSESSMENT				
DDL Ref		Haz Ref No	Description		Type	Consequence	Likelihood	Risk	Mitigative Action Rqd; Party Best Able To Manage Risk	arty tisk	Consequence	Likelihood	Alarp Risk
DDL1	Strengthening generally	ENV1	To access the site for strengthening works, temporary access roads will need to be constructed in a SSSI	-	U	3 - moderate impact on local scale	5 - certain	15	Client to arrange permissions. Contractor's temporary works designer to limit damage. All areas to be made good after completion with original topsoil material to enable regeneration and the method to be agreed with relevant stakeholders.		2 - moderate impact on local scale	5 - certain	ę
DDL3	Pier strengthening	ENV2	With either option, existing ground will have to be excavated within the SSSI.		U	3 - moderate impact on local scale	5 - certain	15	Client to arrange permissions.		2 - limited impact on local scale	5 - certain	10
6100	Intrusive works in reinforced concrete	ENV3	For the Type 3 repairs, reinforced concrete will need to be bricken out within a SSSI area by either HydroDem or hand break-out.	orced ken out .t.	O	3 - moderate impact on local scale	5 - certain	15	Use suitable containment and catchment to contain, collect and dispose of arisings from break-out activity.		 Ilmited Impact on local scale 	5 - certain	5

Uncontrolled when Printed

Appendix F Cost estimate and programme for construction

BAM - Buildability Review & Budget Pricing Report inc. Cost Summary, v3

BAM - Strengthening Work Budget Programme - Two Season, v3.1

BAM - Strengthening Work Budget Programme - Single Season, v3.2

Commentary



COWI

Cairngorm Mountain Funicular Railway Remedial Works Buildability Review & Budget Pricing









Cairngorm Mountain Funicular Railway

Buildability Review, plus Preparation of an Indicative Budget & Programme

Report number: 4012-COWI-r-0101

Client: Cowi UK Limited

Author	
Name:	
Direct line:	
E-mail:	@bamnuttall.co.uk

3	Fourth Issue		31-05-2019		31-05-2019		05-06-2019
2	Third Issue		29-05-2019		29-05-2019		29-05-2019
1	Second Issue		26-04-2019		29-04-2019		29-04-2019
-	First issue		29-03-2019		29-03-2019		29-03-2019
Revision	Status	Author	Date	Verified	Date	Released	Date

© BAM Nuttall Limited ("BAM"). This document (including any enclosures or attachments to it) is confidential and intended for the exclusive use and benefit of the party for which it was produced. This document has been prepared on the basis of the information and documents expressly referenced in it and the assumptions set out in it. It is solely for use for the purpose stated in it, or if none, for the purpose for which it was provided. BAM owes no duty of care whatsoever to any other party under or in connection with the document. BAM accepts no liability whatsoever to any third party whether direct or indirect and whether arising in contract, tort (including negligence), breach of statutory duty or otherwise. Nothing in this statement shall exclude or limit liability which may not be excluded or limited by law. The unauthorised use, disclosure, storage or copying of the document (including any enclosures or attachments to it) is not permitted. If you are not the intended recipient, please inform the sender by return and destroy all copies of it.

Cairngorm 4012-COWI-r0101 31st May 2019 Revision: 3





Table of Contents

Introduction	3
Background and purpose	3
Scope of work	3
Input data	4
Deliverables	4
Concept Development	4
Appendix A – Schedule of Assumptions	

Appendix B – Outline Programme

Appendix C - Budget Price





Introduction

COWI UK Limited have been commissioned by Highlands and Island Enterprise (HIE) to investigate the problems identified with the funicular railway on Cairngorm Mountain and to provide advice on the options available to HIE to rectify these problems.

This advice includes recommendation as to the optimum technical solutions to be used and also to provide an indicative price and programme for undertaking these repairs.

COWI has engaged BAM Nuttall Infrastructure Advisory Services (BAM) to provide assistance with the development of the technical solutions and to provide budget and planning services.

Background and purpose

The Cairngorm Funicular Railway was opened in 2001 and has a 2km route from a base station at an elevation of 635m to a top station at an elevation of 1,097m.

The railway is owned by HIE and until recently was operated under a long-term lease arrangement by CairnGorm Mountain Limited (CML), a subsidiary of Natural Retreats. During inspections in 2018 aspects of the condition of the asset caused concern and COWI has been engaged to carry out a detailed engineering assessment of the railway and to recommend remedial works. Such is the concern about the condition of the asset that the railway was closed to the public in October 2018, with the operator (CML) subsequently placed into administration.

The closure of the railway has attracted nationwide publicity due to the negative impact of its closure on tourism in the Strathspey area and the consequent reduction in employment locally.

It is understood that as the owner of the asset HIE wish to establish whether it is technically and economically feasible to repair the existing asset and will then compare that option with alternatives such as its complete replacement or removal.

COWI have supervised intrusive investigative works and have developed details of the proposed remedial works but given the demanding environmental conditions, access and environmental constraints it is desired to obtain the input of an experienced contractor to develop a budget and programme for this work.

Scope of work

The scope of works undertaken by BAM is;

- Attend site visit with COWI, HIE and Cairngorm Mountain.
- Provide buildability advice to COWI to assist with the selection and development of preferred solutions for each intervention
- Undertake basic planning of the construction operations required to deliver these interventions.
- Prepare an outline programme for the execution of the works
- Engage with their supply chain to determine budget prices for materials or specialist services needed for the delivery of the proposed solutions.
- Develop a budget price for undertaking these works.
- Prepare a list of key assumptions that have been used in the development of the outline programme and budget price.
- · Run a scenario whereby the works are carried out in a single season.

Cairngorm 4012-COWI-r0101 31st May 2019 Revision: 3



COWI

Input data

In undertaking this commission BAM has relied upon the following documents:

- A116993_Rp01_v2 Appraisal Report, plus associated Appendices A to E inclusive.
- A116993 Strengthening extents 190328
- A116993 Strengthening extents layout deck 190328
- A116993 Strengthening extents layout piers 190213
- COWI sketches as follows:
 - o SK01revA
 - o SK05revA
 - o SK12
 - o SK13
 - o SK14
 - o SK15

Deliverables

BAM has prepared the following deliverables, which are included as Appendices to this report:

- Schedule of assumptions used in preparing the programme and budget for the proposed remedial works (Appendix A)
- Outline programme for undertaking the proposed remedial works (Appendix B)
- Budget price for undertaking the proposed remedial works, including a commentary on the degree of accuracy or 'bandwidth' of the budget (Appendix C)
- Examination of the scenario where the works are undertaken in one season (Appendix D).

Concept Development

Based on the work done to date BAM has noted the following areas which it is considered may allow a reduction in the cost and also potentially the time to complete the works. These areas are therefore recommended for further ongoing investigation:

· Disposal of excavation arisings from works to piers and anchor blocks.

Given the significant cost associated with helicopter transport identified in the initial budgeting exercise it is clear that there is significant cost associated with the relocation of this material to the Ptarmigan restaurant area. If it can be distributed locally at the pier and anchor block locations then a saving of more than £200k could potentially be secured.

· Review of foundation details in order to reduce the volume of concrete required.

Currently the foundation design requires a considerable amount of concrete, which is contributing significantly to the cost of the helicopter transport. If this can be reduced then a significant cost and time saving could potentially be available.

 Continue to work with bearing suppliers to try to identify a solution that avoids the need for the introduction of a third central bearing.

Currently a third bearing is needed in the centre of each crosshead in order to provide the lateral resistance that is needed. If through further dialogue with bearing manufacturers it proves possible to remove the need for this bearing or to limit its use to certain sections of the track only then a significant saving in time could potentially be achieved.

Cairngorm 4012-COWI-r0101 31# May 2019 Revision: 3

Appendix A – Schedule of Assumptions

In preparing the outline programme and cost for the works the following assumptions have been made:

- 1 The construction season will run from the last week of May 2020 to the third week in October 2020 and similarly from May 2021 to October 2021.
- 2 Any material placed/stored on the mountain can remain there between the two seasons.
- 3 No flying constraints will be imposed on helicopter movements during this period and adequate space and environs will be provided for landing and take-off.
- 4 Adequate storage and welfare areas will be made available at the Shieling, Lower Carpark and if necessary Ptarmigan.
- 5 Whilst ground disturbance will be kept to a minimum, we have made no provision for other environmental constraints beyond the use of spider excavators, low ground pressure (LGP) equipment and run-off silt screens
- 6 A 2" pump has been allowed for the management of any water inflow into excavations.
- 7 We have made provision for setting aside the top peat for reinstatement at the end.
- 8 We have assumed the ground is sufficiently stable for the excavation sides to be battered, with no need for temporary support equipment.
- 9 We have assumed the soil to be gravel, or weathered rock and there is no excavation in rock
- 10 We have assumed the use of LGP excavation plant below the Sheiling and spider type excavation equipment above it.
- 11 It is assumed that our plant selection can work unhindered below the existing structure. Time does not allow us to assess areas of limited height but we have used low production rates to account for this.
- 12 Notwithstanding our obligation to mitigate noise, we have not made provision for specific noise reduction measures beyond those expected in urban areas.
- 13 Excess excavated material will be left in heli sacks at the Ptarmigan for future use by Cairngorm Mountain
- 14 Excavated material is suitable as backfill
- 15 Average prop lengths is 2.6m+1m cast in, with prop base on the 1st pour
- 16 An allowance only has been made for the prop head arrangement.
- 17 We have made provision for 75mm blinding to prop bases
- 18 There is no constraint on the striking time for formwork and this can be struck the following day.
- 19 Prop plinth, SK01 rev A, has vertical face
- 20 Bagged backfill stays at bases over winter
- 21 Construction tolerances will be designed into the anchor block bearing support frame
- 22 The 25mm bar ends are where we expect them to be in the repairs to the scarf joints and we do not have remove additional concrete to find the ends. We have therefore allowed for removing 2m of the PC beam flange by saw cutting and hand breaking to expose the 25mm bar.
- 23 It has been assumed that prior to strengthening works, the structure load will be transferred to the crosshead using 2nr 200t jacks. When the load is off the bearings they will be unbolted and slid out and replace by the new bearings attached to the existing base plate with the same bot arrangement.
- 24 Some materials are from mainland Europe so there is a procurement risk associated with Brexit, which it is not possible to allow for due to the level of uncertainty.
- 25 The lateral bearing is designed for in situ fit up and construction tolerances
- 26 Access risk for coring rig for lower bearing plate holes

Caimgorm 4012-COW-p-2 31st May 2019 Revision 3

Appendix B – Outline Programme

Attached separately. Titled: 190531 CAIRNGORM FUNICULAR RAILWAY STRENGTHENING v3.1

Cairngorm Funicular Strengthening Work Budget Programme.

Programme commentary:

In planning the Works we had safety concerns regarding the excavation works being incomplete over the ski season. We have therefore resourced the activities to mitigate against this risk.

The logic behind the sequence is that the props should go in first because:

- a. They stabilise and strengthen the support prior to any superstructure strengthening.
- b. The excavation is backfilled in time to permit the erection of the access scaffold to the pier heads and the first cross beam locations.

Not all of the prop bases can be excavated at the same time because the excavations will be left open and exposed to the weather, we have therefore planned on progressing two at a time.

The bearing, lateral and pot/spherical, replacements go in prior to the strengthening and hence stiffening of the beams. The jacking of the beams off the crosshead is to remove the load from the existing bearings, to facilitate their removal. There is a risk that the bearing encasement may be fused to the base plate and this risk should be considered when compiling the project risk register.

T3 to T3, 25mm rebar repair will be carried out prior to the scarf joint strengthening as these two details have an interface to manage.

The bearing, scarf joint and T3 repairs have been combined, insofar that they are to be done at the same time to minimise access arrangements eg the scaffold will be erected and taken down once at each location, rather than a protracted access hire.

We have been cognisant of the helicopter time and movements and the plan is based on one helicopter. This will require optimal time and motion planning at a later date.

Appendix C - Budget Price

Our estimated budget is $\pm 5.6m$ with a +/- 20% margin of error. A breakdown of these costs is included in this appendix.

The above excludes the pot/spherical bearing costs as details of these are necessary for a material quote to be included in our estimate. Notwithstanding this, we have include the cost of the fixing effort ie equipment and labour to replace the bearings.

We have included 5% for Risk and 3.7% RPI over the period.

Caimgorm 4012-COWI-p-2 31st May 2019 Revision 3





Cairngorm Funicular Railway Remedial Works Buildability Review & Budget Pricing

WORK COST SUMMARY - TWO SEASONS

	Direct Work Costs			1 COLUMN
1	SK01 Pier head propping (46 locations @ 43 piers)	46	nr	
2	Anchor Block Additional Bearings			
a)		6	nr	
b)		4	nr	
3	SK05 New bearing replacement (2nr per pier)			0
a)				
	(excl. material costs of spherical / pot bearings)	196	nr	
b)	Install new lateral restraint guide	97	nr	
4	SK11 Scarf joint reinforcement steel replacement	26	nr	12110
5	External PCC beam shear reinforcement			
a)		360		
b)		166	nr nr	
c)		20	nr	비귀화
		20		
	Total Direct	Net Cost		
	Helicopter costs included in above direct net costs			
	Preliminaries & General Condition Costs			
	Season 1 - May 2020 to Oct 2020			
	Season 2 - May 2021 to Oct 2021			
	NEL 1007 EPER MEL 1897			
	Total Indirect	Net Cost		
	Total Indirect	Net Cost	_	
	Total Indirect			
	Other identified costs (Insurances, inflation eff			
	Other identified costs (Insurances, inflation eff	ects, etc.) @ 12.2%		

Revision 3a

Appendix D – Single Season Scenario

As part of the exercise to consider the cost of undertaking the strengthening works to the funicular railway BAM has also looked at the scenario whereby the works are undertaken over a single season.

The benefit of this approach is that it allows works to be completed significantly earlier than would otherwise be the case. However, it is more sensitive to a poor weather season than the baseline approach and carries the risk that in the event of a bad year the works may not be completed before the winter arrives and work has to be suspended.

Our conclusion is that it is possible to complete the works within a single season by deploying sufficient resources, including a second helicopter, and by extending the working period into the shoulder months when weather conditions are less favourable.

Our analysis shows that it should be possible to complete the works in a single season for a similar cost as for two seasons.

Caimgorm 4012-COWI-p-2 31st May 2019 Revision 3

Appendix D1 – Schedule of Additional Assumptions – Single Season

In addition to the assumptions noted in Appendix A above, a number of further assumptions should be noted in relation to this scenario:

- 1 The construction season will run from the start of April 2020 to the end of October 2020
- 2 It will be possible to operate two helicopters at once during the initial period of prop installation.
- 3 A purpose built rail mounted lifting equipment will be developed and deployed to support the squads working on bearing replacement and mechanical strengthening.

Caimgorm 4012-COWI-p-2 31st May 2019 Revision 3

Appendix D2 –

Outline Programme – Single Season

Attached separately. Titled: 190531 CAIRNGORM FUNICULAR RAILWAY STRENGTHENING v3.2

Cairngorm Funicular Strengthening Work Outline Programme - Single Season

Programme commentary:

The commentary noted in general also applies to this scenario; the key difference being that in order to achieve the works within a shortened period a second helicopter will need to be deployed and the number of squads used increased. Specifically, in order to complete the works in a single season the following squads would need to be deployed in the field:

- Squad Type 1:
 - o Propping to piers
 - o 3 No. squads required
 - o Each squad works on two foundations at the same time.
- Squad Type 2:
 - o Bearing replacement
 - o Scarf joint mechanical strengthening
 - o Cross beam mechanical strengthening
 - o 7 No. squads required
- Squad Type 3:
 - o Concrete strengthening at scarf joints
 - o 1 No. squad required
- Squad Type 4:
 - o Provision of scaffold access to above teams
 - o 1 No. squad required
- Squad Type 5:
 - o Logistics support to above teams
 - o 1 No. squad required

Appendix D3 – Budget Price – Single Season

Our estimated budget is £5.6m with a +/- 20% margin of error.

Once again this excludes the pot/spherical bearing costs as details of these are necessary for a material quote to be included in our estimate.

As part of the analysis of this option we have undertaken an assessment of the impact of increasing resource levels in order to complete the works in a single season and the additional support that will be required to ensure that the teams undertaking the works can operate at maximum efficiency.

Key changes are as follows:

į,

- Extension of the season in order to allow works to be completed within the period, with the sequencing set so as to minimise the risk of weather delay during the shoulder periods.
- Requirement for full time helicopter support for a period of 10 weeks, with a second visiting helicopter in addition over this period in order to meet demand.
- Increase in levels of supervisory staff and supporting personnel, plus associated levels of accommodation and general site plant.

Caimgorm 4012-COWI-p-2 31st May 2019 Revision 3






Cairngorm Funicular Railway Remedial Works


Buildability Review & Budget Pricing


WORK COST SUMMARY - ONE SEASON


	Direct Work Costs			
ĺ	SK01 Pier head propping (46 locations @ 43 piers)	46	nr	
2	Anchor Block Additional Bearings			
a)	SK12 Anchor Blocks 0, 65 & 78	6	nr	
b)	SK13 Anchor Blocks 14 & 29	4	nr	
5	SK05 New bearing replacement (2nr per pier)			
a)	Replace existing spherical / pot bearings	400		No.
	(excl. material costs of spherical / pot bearings)	196	nr	
b)	Install new lateral restraint guide	97	nr	
	SK11 Scarf joint reinforcement steel replacement	26	nr	
	External PCC beam shear reinforcement	- × 1		
a)		360	nr	line
b)	SK15 Ext shear reinforcement @ 1st crossbeam	166	nr	
	SK15 Ext shear reinforcement @ 2nd crossbeam	20	nr	
	Preliminaries & General Condition Costs Prelims - April 2020 to November 2020 (excl helicopter Helicopter costs (2nr heli squads covering f/time + p/ti	882		
	Total Indirect			
		Net Cost		
	Total Indirect Other identified costs (Insurances, inflation et	Net Cost		
	Total Indirect Other identified costs (Insurances, inflation er O&F	ffects, etc.)		
	Total Indirect Other identified costs (Insurances, inflation er O&F	Net Cost		


Revision 3b











Appendix F -- Single Season Programme Commentary: Summer 2020

Commentary from BAM to reduce cost estimate of remedial works;

- Foundation size same comment as for two season option.
- Foundation depth same comment as for two season option.
- Review of bearing replacement options same comment as for two season option.

Assumptions by BAM for consideration and appreciation by HIE;

- Any flying constraints over the site are unknown to BAM. Any constraints could be more severe for the single season option as at peak periods two helicopters will need to operate.
- Adequate areas to be made available for the provision of welfare and storage facilities at Shieling, carpark and possibly ptarmigan. These areas to be identified by HIE. Note that this provision will need to be greater for the single season option than the two season option due to the larger labour force and the need for concurrent activities.
- BAM have assumed purpose built rail mounted lifting trolleys will be used for bearing replacement and mechanical strengthening operations. This is stated as necessary to the finding that the one season option is the same cost as the two season option.
- As with the two season option, BAM states small risk from Brexit outcome against procurement risk from Europe.
- As with the two season option, there is a risk of bearings fused to existing structure. A trial
 on-site by HIE could mitigate this risk and identify any unforeseen issues at this stage with
 bearing replacement in general.
- Post completion, any excess excavated material will be stored for HIEs use adjacent to the ptarmigan building. HIE need to consider this. No provision to remove off excess material off site has been allowed.

Comments on BAMs Assumptions:

1 – Construction period - Early April 2020 to end of October 2020. This is a longer season than considered for the two season option but allows for 3 weeks mobilisation and demobilisation at the beginning and end of the season.

7 - BAM intend to re-use top soil for environmental restraints.

8 - Battered sides for an excavation may lead to an extremely large hole, especially up the hill.

9 - No hard breakout required. Backfill material only for foundations.

10 – Use of plant equipment seems sensible. Difficultly in sourcing enough of a single machinery type may be encountered. This risk is mitigated by consideration of purpose built rail mounted lifting trolleys on the existing funicular.

11 - A sensible allowance is assumed for poor access under existing structure

13 - No allowance for removal of excess excavated material.

15 - Prop costs have been averaged by length. Seems logical for cost estimating exercise.

22 - No hydro demolition is considered for T25 bar repairs.

23 – Bearing replacement assumes use of existing taper plates and upper tang plates with existing bolt hole diameters and spacing. Temporary jacks are assumed to be adequate to remove load off superstructure.

- 25 Adequate tolerance allowance on lateral bearings is required during detailed design.
- 26 Access of equipment for additional lateral bearing and drilling requirement is a risk.

28 - A key assumption for the budget price, mentioned again in Appendix C.

Comments on Programme in general:

- The programme assumes a 5 week tender period starting in early August with Contract award on 20th September 2019. However early activities are not shown as being critical to the completion date.
- Procurement of bearings is shown as 10 weeks. This appears optimistic given the quantities involved. However the programme shows approximately 6 months being available before bearings have to be delivered.
- The start on site is in early April beginning with a 3 week mobilisation period. Bearing
 replacement works commence in late April. This involves much greater weather risk than the
 late May start considered in the two season option, and potentially overlaps with the ski
 season.
- Work is carried out initially on five work fronts, expanding to seven work fronts later.
- Where pier propping is to be carried out, this is undertaken prior to other works.
- Where T25 bars are to be connected, this is undertaken prior to shear strengthening.
- Bearing replacement is followed immediately by shear strengthening i.e. only short requirement for scaffold tower at any location.
- Completion is shown at the end of November following a 3 week demobilisation period and 5 weeks programme float.

Appendix F – Two Season Programme Commentary: 2020-2021

Commentary from BAM to reduce cost estimate and reduce programme;

- Foundation size Reduce volume of concrete and thus weight for delivery by helicopter and number of visits. This can be reviewed in detailed design and volume of concrete/weight of material kept to a minimum.
- Foundation depth reduce excavation volume. Depth of excavation shall be kept to a minimum during detailed design.
- Review of bearing replacement options Eliminate requirement for the additional lateral guide at some locations. Extensive work has been undertaken on this. A project wide result was not found. Detailed design can review a spilt bearing design approach for different areas.

Assumptions by BAM for consideration and appreciation by HIE;

- A materials store over winter months is assumed to be available on site at the Cairn Gorm Mountain resort. This includes back fill material.
- Any flying constraints over the site are unknown to BAM are not considered during the construction period.
- Adequate areas to be made available for the provision of welfare and storage facilities at Shieling, carpark and possibly ptarmigan. These areas to be identified by HIE.
- BAM states small risk from Brexit outcome against procurement risk from Europe.
- Risk of bearings fused to existing structure. A trial on-site by HIE could mitigate this risk and identify any unforeseen issues at this stage with bearing replacement in general.
- Risk of integrity and thus re-use of existing taper plates. Detailed inspection and a trial conducted by HIE on worse areas could mitigate this risk.
- Post completion, any excess excavated material will be stored for HIEs use adjacent to the ptarmigan building. HIE need to consider this. No provision to remove off excess material off site has been allowed.

Comments on BAMs Assumptions:

1 – Construction period – Two summer seasons. Site activity from last week in May to third week in October. A short season, but realistic.

7 - BAM intend to re-use top soil for environmental restraints.

- 8 Battered sides for an excavation may lead to an extremely large hole, especially up the hill.
- 9 No hard breakout required. Backfill material only for foundations.
- 10 Use of plant equipment seems sensible.
- 11 A sensible allowance is assumed for poor access under existing structure
- 13 No allowance for removal of excess excavated material.
- 15 Prop costs have been averaged by length. Seems logical for cost estimating exercise.
- 22 No hydro demolition is considered for T25 bar repairs.
- 23 Bearing replacement assumes use of existing taper plates and upper tang plates with existing bolt hole diameters and spacing. Temporary jacks are assumed to be adequate to remove load off superstructure.
- 25 Adequate tolerance allowance on lateral bearings is required during detailed design.
- 26 Access of equipment for additional lateral bearing and drilling requirement is a risk.
- 27 A reasonable assumption is made.

Comments on Programme in general:

- Pier strengthening works are undertaken first and props are installed including excavation, foundation casting and back filling.
- Two prop locations are worked on simultaneously.
- Bearings, T25 repair (if required) and Shear strengthening undertaken at one location all at same time – i.e. only short requirement for scaffold tower at any location.
- Bearings replaced prior to shear strengthening of scarf joints and beams.
- T25 repairs prior to shear strengthening of scarf joints.
- Use of one helicopter only assumed.
- Assumes access to site 7th Oct.
- Procurement of 3 months with 4 months float for bearings, metalwork and props means a delay in awarding contract will not affect completion date.

Other considerations:

- Consideration of use of the maintenance trolley was given but the temporary works and works needed to protect the existing funicular has high risks.
- Much time was spent by BAM looking at phased approach to the lower half and upper half and it was considered unachievable. Too many interfaces for differing intervention solutions increased risk.